BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2015-16/RD/WORK_INDENT19170/CALL-2

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/03/2015-16, Date: 22.01.2016

Improvements to Roads and Drains at Shabarinagar in Ward No.6 Byatarayanapura Sub Division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of Y R SRIDHAR		
				In Figures		In Words
1	116.73	KSRB 2-1.1: Earth work in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications, Specification No KBS 2.1(a) / 2.3.1.P. No. 5/ Item No. 2.1/ PWD SR 2015-16	cum	140.0	16342.20	Rupees One Hundred Forty Only
2	1650.83	Removing B.S Slab of Drain and stacking Page No. 25/ Item No. 5.32/ PWD SR 2015-16	Sqm	50.0	82541.50	Rupees Fifty Only
3	1650.83	Refixing stone slabs of drains and pointing in C.M (1:3) Page No. 25/ Item No. 5.33/ PWD SR 2015-16	Sqm	60.0	99049.80	Rupees Sixty Only
4	550.28	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar(1:6) including fixing curing etc, complete -do- 7.5 cms thick Page No. 28/ Item No. 5.31.1/ PWD SR 2015-16	Sqm	650.0	357682.00	Rupees Six Hundred Fifty Only
5	3335	KSRRB 300-49: scarifying bituminous course 50mm to 75mm thick along with premix carpet/surface dressing by manual means without disturbing the base and stacking of the debris materials within a lead of 100 meters including cost of all labour charges complete as per specifications. MORTH chapter 3, No. 155/ Item No. 19.55/ PWD SR 2015-	Sqm	50.0	166750.00	Rupees Fifty Only
6	667	KSRRB M400-17: Providing, laying spreading and compacting graded stones aggregate to wet mix macadam specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying, in uniform layers with paver in sub base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH specification NO. 406, No. 154/ Item No. 20.18/ PWD SR 2015-16	Cum	1711.75	1141737.25	Rupees One Thousand Seven Hundred Eleven and Seventy Five Paise Only
7	3335	KSRRB 500-4: providing and applying primer coat from 7.5 to 9.8 kg and 9.8 to 12.2kg per 10 sqm for surfaces of low and medium porosity respectively over prepared surface of granular base with cut bank M.C-70 or any other bitumen mixed with diesel at 10 kg per 10 sqm heated in bitumen boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM of machineries complete as per specificationsDo- Medium Porosity MORTH chapter 5, No. 157/ Item No. 21.5/ PWD	Sqm	50.0	166750.00	Rupees Fifty Only
8	83.38	KSRRB M500-18: Providing and laying semi dense bituminous concrete 25mm thick with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 4.5 to 5% of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem roller to achieve the desired compaction as per MORTH specifications clause No. 500.8 complete in all respects as per specifications. P. No. 159/ Item No. 21.21.1/ PWD SR 2015-16	Cum	9250.0	771265.00	Rupees Nine Thousand Two Hundred Fifty Only
9	116.73	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km (Page No.123,	Cum	67.0	7820.91	Rupees Sixty Seven Only
					2809938.66	

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

5/5/16

05/05